


# Dish-Stirling Hybrid Receiver Development

---

## *A Collaboration of:*

SunLab  
CFIC  
Continental Heberle




## *Presented by:*

Jim Moreno  
Sandia National Laboratories

# Project Background

- **Hybrid Receiver Concept**

- Fuel-augmented solar
- Not either/or
- Four major components...




# Project Background

---

---

- **Motivation: industry-identified need**
  - Utilities:
    - capacity payments
  - Remote applications:
    - nights/cloudy days
    - single power converter



# Project Definition

- **Objective: develop a 75-kW<sub>t</sub> throughput hybrid receiver for dish-Stirling applications**

FY	FTEs	DCs(\$k)	Activities
96 (8/96 start)	1.0	20	1/6-scale design, build, & test.
97	1.5	100	
98	2.0	100	1/6-scale mod & test.
99	2.0	200	Full-scale design.
00	2.9	167	Full-scale design, build, & test.
01 (10/01 end)	2.3	172	

# Hybrid Receiver Development Goals


---

---

- **Desired receiver characteristics:**
  - Fuel-augmented solar (not either/or)
  - 75 kW<sub>t</sub> throughput at 750 C
  - 75% thermal efficiency at design point
  - Low emissions
  - Cost competitive with diesel augmentation

# Hybrid Receiver Development Approach



- **Clean-sheet design**
  - Extensive CFD and FEA modeling (heat transfer, pre-ignition, stress)
  - Manufacturers involved to assure manufacturability and low cost
  - Tightly integrated for efficiency
  - Stud-welded pin fins: least expensive extended area
  - Metal matrix burner selected for low emissions and compactness
- **Development process**
  - MS Project planned & tracked
  - Natural gas initially; option for other fuels
  - 1/6-scale device first, for proof of concept



# Hybrid Receiver Development Progress

- 1/6-scale accomplishments


- Nox~18 ppm
- CO~40 ppm
- System model validated...



# Hybrid Receiver Development Progress

- **Full-scale receiver accomplishments**

- Tested at:
  - 25 to 100+ kW<sub>t</sub> firing rate
  - 12 to 80° elevation
  - Up to 750C heat pipe temperature, 640C preheat
- Starts smoothly, stable, no pre-ignition or detonation



# Hybrid Receiver Development Progress

---

---

- **Other accomplishment details**
  - Developed manifold giving < 1% fuel/air variation
  - Developed high speed stud welding process
    - Rapid 100% ultrasound inspection
    - Acceptable weld quality and distortion
  - Designed successfully to prevent thermal wracking
  - Manufacturer's cost estimates (vs \$7500 diesel)
    - Combustor/recuperator: \$4150 @ 10<sup>4</sup>/y
    - Pin-finned cylinder: \$ 1170 @ 10<sup>4</sup>/y
  - 3 papers, 1 patent application

# Hybrid Receiver Status/Issues

---

---

- **Testing**

- Check instrumentation to close energy balance
- Emissions
- Combined solar/gas

- **Hardware**

- Wick hot spot has appeared – may be fixable
- Address indication of occasional leakage at critical seal
- Evaluate lifetime potential
- Alternate fuels